

# Starlink + Solar Installation Guide

Sample document showing detailed deployment procedure and acceptance testing

**Prepared by:** Levie Lameyra

Sample / Mock Project - For portfolio demonstration only.

No real client, personal, or confidential data is included.

## 1. Overview

This guide describes a standard field procedure for installing Starlink satellite internet with a solar-backed power system for remote connectivity. All site details are fictional and privacy-safe.

## 2. Scope

Includes site assessment, mounting, cable routing, solar wiring, router setup, testing, and handover documentation.

## 3. Tools and Materials

Category	Items (Sample)
Tools	Screwdrivers, wrench set, measuring tape, cable ties, drill (if mounting), multimeter
Starlink	Dish + router, power cable, dish cable, mount (tripod/pole/roof)
Solar/Power	Solar panel(s), charge controller, battery, fuses/breakers, grounding kit, weatherproof conduit
Network (Optional)	Ethernet adapter, external router, PoE injector (if needed)

## 4. Pre-Installation Checks

Complete the checks below before installation:

Check	Acceptance Standard	Sample Result	Notes
Sky visibility	Clear view; minimal obstructions	PASS	No obstruction detected in app scan
Mount area	Stable surface; wind-resistant	PASS	Pole mount selected; anchors tightened
Cable route	Secured and weatherproof	PASS	Conduit used; drip loop added
Power readiness	Controller + battery verified	PASS	Battery 12.7V prior to load
Grounding plan	Surge/lightning protection	PASS	Ground rod + bonding strap included

## 5. Installation Procedure

### 5.1 Mount the Starlink Dish

- Assemble mount and anchor securely using appropriate bolts/anchors.
- Place dish with clear sky view; avoid trees/buildings.
- Confirm dish cannot shift under moderate force.

### 5.2 Route and Secure Cabling

- Route dish cable through conduit or clips.
- Add drip loop before entry points.
- Label both ends: DISH and ROUTER.

### 5.3 Solar Wiring (High-level)

- Connect panel to charge controller (verify polarity).
- Connect battery to controller via fuse/breaker.
- Connect router load using regulated output or inverter (if AC).

#### 5.4 Configure Starlink

- Power up router.
- Use Starlink app to set Wi-Fi name and password.
- Allow automatic alignment and calibration.

### 6. Testing and Acceptance (Sample Results)

Test	Acceptance Criteria	Sample Result	Status
Download speed	>= 50 Mbps	128 Mbps	PASS
Upload speed	>= 8 Mbps	18 Mbps	PASS
Latency	<= 60 ms	29 ms	PASS
Obstruction check	No persistent obstruction	None detected	PASS
Battery voltage (idle)	12.4V to 13.2V	12.7V	PASS
Charge current (sun)	> 0A	8.1A	PASS
Stability observation	No reboots for 60 min	Stable 90 min	PASS
Documentation	Complete and privacy-safe	Uploaded	PASS

### 7. Handover Package

Upload the following (privacy-safe):

- Photos: mount, cable routing, solar wiring (no serial numbers)
- Completed asset tracker entries
- Test results sheet
- QA/QC forms signed using initials only

Privacy Note: Do not include addresses, client names, account IDs, or serial numbers in portfolio versions.